

## THE BILL OF QUANTITY FOR PARTITION WALL OF TWO MHD NURSES ROOM

S/N	ITEM DESCRIPTION	QTY	UNIT	RATE (TZS)	TOTAL AMOUNT(TZS)
1	<b>MOBILIZATION AND DEMOBILIZATION</b>				
	Allow for mobilization and demobilization of equipment and materials	1	item		
2	<b>PARTITIONING WALL</b>				
A	Supply and fix a 50mmX100mm vertical timber (Pinus) at 1000mm intervals	45	M		
B	Supply and fix a 75mmX50mm horizontal timber at 400mm intervals	81	M		
C	Supplying and fixing of gypsum boards to timber partitioning wall	82	Sm		
D	Skimming	82	Sm		
3	<b>DOOR</b>				
A	Supply and fix a 875mm X 2200mm light aluminium sliding door as per drawing, the cost shall include frame and all necessary accessories like; door hinges, locks, painting etc.	2	Nr		
B	Supply and fix single leaf door overall size 875mm X 2200mm high as per drawing, the cost shall include frame and all necessary accessories like; door hinges, locks, painting etc to match the exiting doors in the entire building.	2	Nr		
4	<b>ELECTRICITY AND DATA</b>				
	Supply and fix following electrical items				
A	2.5sqmm flexible cable	5	m		

B	Twin square metal box	2	Nr		
C	Twin switch sockets	2	Nr		
D	¼" Cable trunk	6	Nr		
4	<b>WORKING TOP/GRANITE AND CABINETS</b>				
	<b>Supply and fix the following items as per drawing</b>				
A	Supply and fix drawers in laboratory and vaccination room, the cost shall include all necessary items required during fixing	8	Nr		
B	600mm wide, 25mm thick granite top to match the existing ones in the entire room	6	Sm		
5	<b>FINISHING WORK</b>				
	<b>(GOLD STAR, SANDOLIN or approved equivalent)</b>				
A	Skimming	82	Sm		
B	Apply two coats of approved paint on a partition wall	82	Sm		
C	Apply one coat of approved paint to all scratches due construction activities as per Engineer's instructions	30	Sm		
D	Skirting to partition wall	30	M		
	<b>SUB TOTAL</b>				
	<b>18% VAT</b>				
	<b>GRAND TOTAL INCLUDING 18% VAT</b>				